SUTHERLAND DISTRICT COUNCIL HOUSING & TECHNICAL SERVICES DEPT

PROPOSED HOUSING SITE SUTHERLAND ROAD, DORNOCH

SITE INVESTIGATION &
FOUNDATION RECOMMENDATIONS

SCOTT WILSON KIRKPATRICK & PARTNERS (SCOTLAND)
CONSULTING CIVIL & STRUCTURAL ENGINEERS
BANK OF SCOTLAND BUILDING
TULLOCH STREET
DINGWALL
IV15 9JZ

PROPOSED HOUSING SITE SUTHERLAND ROAD, DORNOCH

SITE INVESTIGATION

1. INTRODUCTION

On the 17 February 1987, Sutherland District Council invited Scott Wilson Kirkpatrick & Partners (Scotland) to carry out a site investigation at a site adjacent to the Cathedral Hall on Sutherland Road, Dornoch and to report on the type of foundations that would be required for a proposed housing development.

The proposed development is that shown on the District Council's Drawings Nos. H948, H804 and H863 for single storey, timber framed, two and three apartment, semi detached houses, along with the access roads.

2. SITE INVESTIGATION

Six trial pits were excavated by means of a JCB on Thursday 5 March 1987. A layout of the pits is shown in Figure 1. It was the intention that all pits be excavated to a depth of 3.00 metres below existing ground level, but problems were encountered with stability and some had to be terminated sooner.

A description of the materials found in each of the pits is given in the Trial Pit Records, Figures 2, 3 and 4.

Standpipes were inserted in Trial Pits 3 and 5.

Two representative samples, one from Pit 1 and one from Pit 4, were taken to the Highland Testing Services Ltd laboratory to determine their particle size distribution.

The results of the tests are shown in Figures 5, 6, 7 and 8.

3. GROUND CONDITIONS

The site is generally lying in a shallow hollow with ground levels lying between 6.00 metres and 8.00 metres at the edge of a raised beach area. The area is overlain by a layer of organic topsoil, varying in thickness between 0.75 metres and 1.40 metres, averaging just less than 1.00 metres.

Below the organic topsoil, in the area adjacent to Sutherland Road, lies a layer of loose to medium dense fine sand of varying thickness between 0.70 metres and 1.10 metres. This layer thins out and does not appear in the pits at the north of the site.

Below the layers of organic topsoil and fine sand lie layers of coarser yellowish and brown sand.

Water was encountered in the 4 lower lying pits, at depths of between 1.0 and 2.0 metres which impaired their stability.

Water levels in the standpipes record an average depth of 0.20 and 1.60 metres for pits 3 and 5 respectively.

4. CONCLUSIONS

From the visual examination of the underlying layers of sand and from the laboratory classification, we are of the opinion that the area, once the organic topsoil had been removed and replaced, would be capable of supporting the proposed housing development and accordingly have drawn up recommendations for ensuring that this is achieved.

5. FOUNDATION RECOMMENDATIONS

We would recommend that the following be carried out in order that safe and adequate foundations are provided for:

a) Housing

- (i) Excavate and completely remove the layer of organic topsoil and expose the layer of fine sand. This should be carried out over an area assuming a 45° dispersal of load from the foundations down to the fine sand layer.
- (ii) The area to be made up to appropriate correct levels by importing granular fill material and compacting it in place on top of the sand layers.

 A geotextile separator should be placed over the fine sand prior to filling, in order to assist compaction. A suitable specification is given below:

Imported fill material shall consist of crushed or uncrushed gravel, stone, rockfill, crushed concrete or slag or natural sand, or a combination of these. It shall be well graded with a maximum particle size of 100 mm and not more than 10% passing the 75 micron sieve. It shall be compacted in accordance with Table 6/2 of the Department of Transport's Specification for Road and Bridge Works, save that the first layer may be 400 mm thick.

The geotextile shall be "Lotrak 16/15" or similar approved laid in accordance with the manufacturer's instructions.

(iii) A raft foundation as shown in Figures 9, 10 and 11 should then be provided for the houses.

b) Access Roads and Car Parks

- (i) The areas below the access roads and car parks should be cleared of any large vegetation and a geotextile separator placed directly onto the existing surface, provided the minimum 450 millimetre road pavement construction can be achieved.
- (ii) The area should then be made up to the appropriate correct levels by importing granular fill material and compacting it in place on top of the geotextile separator.

The specification should be identical to that used for the area under the houses.

The width of area to be treated should be determined assuming a 45° dispersal of load from the road pavement through the infill material.

c) <u>landscape Areas</u>

i) Areas outwith the houses and access roads should be made up to the correct levels using suitable filling material laid directly onto the existing ground. Topsoil to a minimum depth of 100 mm should then be provided.

The above specifications would provide adequate foundations for the individual parts, but some differential settlement of the access roads and car parks may be expected, due to compression of the topsoil. This can be mitigated by filling early and delaying final surfacing to the end of the job and providing strong drainage falls.

It may, however, be more appropriate to treat the whole site similarly, based on the specification for the housing areas, for the following reasons:

- (1) Control of filling operations would be much easier to monitor.
- (2) Alterations to layout in the future could easily be accomplished.

- (3) Differential settlements would be minimised.
- (4) The cost of treating the whole area may turn out to be competitive with that for doing separate parts. Although more material would have to be removed and replaced, the operation would be much simpler and may result in a cheaper cost.

Further consideration should also be given to carrying out the work of removal and infilling as a separate contract in advance of any building work. This could then be accomplished as either a long term or short term contract, depending on finances available.

Method of exc	cavation	JCB Ex	cavator	Location	ate commenced	Record	of	
Dimensions o			x 1.0	Ground level (m O D) 6.30	5/3/87	TRIAL	PIT 1	
Samples and i Depth (m)	n situ tests Type	Water depti (m)	Date and depth (m)	Description of strata			D level	Leg
			0.75	Loose black topsoil overl 150 mm loose white fine s			5.53	
			1.40	Very wet and foul smellin	ng fibrous		4.90	不 万 不
SAMPLE	E A			Loose saturated blue/grey sand with occasional larg cobbles				
			2.30	End of Trial Pit	,		4.00	<u>, o</u> ,
	-							
Remarks: P	it ha	d to h	e aband	loned at 2 30 as side kent	folling	 in		

marks: Pit had to be abandoned at 2.30 as side kept falling in and soil in base was completely saturated.

Method of exca			cavator		Location			Date commenced	Reco		
2.0 X 1.0							AL PIT 2	<u></u>			
Samples and in Depth (m)	situ tests Type	Water depth (m)	Date and depth (m)			Descrip	ition of strata			O D ievel (m O D)	Leg- end
				Loo	se black	tops	oil				K
			0.75							5.49	<u>//</u>
			1.30	Loos		ated :	yellowis	sh coarse		4.94	
				sand				ey fine rge round			0
			2.40		bles					3.84	
			3.00	Loos	se satur	ated 1	orown cc	parse sand		3.24	
					End	of Tı	cial Pit	;			
											İ
				•				,			
				•							
emarks:											

Remarks:

Side of pit kept falling in. Water entering around the 5.20 m level.

TRIAL PIT RECORDS Scale 1:50 For explanation of symbols and abbreviations see Key Sheet	87504
Proposed Housing Site Sutherland Road, Dornoch	Fig 2

Method of ex	ravation c	ICB Exc	avator		Location		Date commenced	Reco	_	
Dimensions o					Ground level (m. C	o 0 6.07	5/3/87	TRI	AL PIT 3	
Samples and in situ tests Water depth Date and				Description of strata			O D level	Leg-		
Depth (m)	Туре	(m)	depth (m)							//
		, <u> </u>		400	mm loose b	lack topso	il overlyi	ng		
*** ****				200	mm loose w	hite fine s	sand over-			
-				lyir	ig fibrous	black organ	ic soir		F 07	\ <i>Y</i>
			1.00						5.07	//
				Medi	um dense w	et blue/gre	ey fine			0
			1.60	sand	l with occa	sional medi	ium cobbles	3	4.47	.0
						aturated bi	rown			• • •
		mana and and an		medi	um/coarse	sand			3.57	
			2.50							
					End o	of Trial Pi	t			
		* **								
								į		
·		·								
										
									•	
D	77 - 3 -		ho ob	ondo	nod at 3 5	7 m as side	es kent fa	 11ir	ng in.	

Remarks: 1. Hole had to be abandoned at 3.57 m as sides kept falling in.

2. Water started entering around the 4.47 m level.

3. Stand pipe installed.

Method of exc	avation J(CB Exca	vator	Location	Record of TRIAL PIT 4	Ł
Dimensions of	trial pit (m	1 2.0 x	1.0	Ground level (m O D) 6.24 5/3/87	O D level	Leg-
Samples and in	n situ tests	Water depth	Date and	Description of strata	(m O D)	end
Depth (m)	Туре	(m)	depth (m)			1/
				Loose black topsoil		//
						大V
			1.00		5.24	
				Medium dense wet white fine sand		
				(becoming saturated towards		
			1.70	bottom)	4.54	• • .
SAMPL	- D			to the design of the company of the		
SAMPL		***		Medium dense saturated brown medium/coarse sand	7 61	
			2.60	medium/coarse sand	3.64	
				End of Trial Pit		
				•		
						1

Pit had to be abandoned at 3.64 m level as sides Remarks: 1. kept falling in. Water started entering hole around the 4.30 m level TRIAL PIT RECORDS

Scale 1:50

For explanation of symbols and abbreviations see Key Sheet Lab Ref No 87504

Proposed Housing Site Sutherland Road, Dornoch

3

Fig

Method of exi	cavation J	CB Exc	avator	LOCATION TO THE TOTAL TO THE TOTAL T	cord of	
Dimensions o			x 1.0	Ground level (m O D) 7.39 5/3/87 TI		5
Samples and i	n situ tests Type	Water depth (m)	Date and depth (m)	Description of strata	O D level (m O D)	Leg- end
				Loose black topsoil		
			0.85		6.54	Z
				Loose to medium dense dry yellowish fine/medium sand with occasional large round cobbles		0
			2.40_		4.99	0
			3.00	Medium dense dry yellowish medium/coarse sand	4.39	
				End of Trial Pit		-
					•	
					·	

Sides of pit stood up well and remained dry. Stand pipe inserted. Remarks: 1.


Method of ext				Location E/7/07 TDI	AL PIT 6	,
Dimensions o	f trial pit (m	0.2.0 x	1.0	Ground level (m 0 D) 7 • 35 37 37 07 171.	r	
Samples and i	n situ tests Type	Water depth	Date and depth (m)	Description of strata		Leg- end
Depin (in)	Туре			Loose black topsoil		Z
			0.85		6.50	\sum
				Loose dry yellowish fine/medium sand with occasional large round cobbles		0
			2.40		4.95	5.
			7 00	Medium dense dry yellowish coarse sand/fine gravel	4.35	•
			3.00	End of Trial Pit		
			4			

Remarks:

Sides of pit remained reasonably intact and dry.

TOTAL DIT DECODES	Lab Ref No
TRIAL PIT RECORDS Scale 1:50 For explanation of symbols and abbreviations see Key Sheet	87504
Proposed Housing Site Sutherland Road, Dornoch	Fig Z _I

HIGHLAND TESTING SERVICES LTD.




(Inverness)—

42a SEAFIELD ROAD LONGMAN INDUSTRIAL ESTATE INVERNESS Telephone (0463) 225844 MATERIALS TESTING ENGINEERS AND CONSULTING TECHNOLOGISTS

	SAMPLE REF. 5231
CLIENT Scott, Wilson, Kirkpatrick Ltd	MATERIAL Sand (grey)
CONTRACT Housing Scheme, Dornoch	SUPPLIER
LOCATION	SOURCE
DATE RECEIVED 5.3.87	B.S. APPLICABLE

AGGREGATE GRADING ANALYSIS SAMPLE NO..

B.S. Sieve Size	Cumulati	ve Percentages Passing
Metric		Spec.
75mm		
63mm		
50 mm		
37.5 mm		
28 mm		
20 mm		
14 mm		
10 mm		
6.3 mm		
5 mm		
3.35 mm		
.2.36 mm		
1.18 mm		
mىر 600	100.0	
425	99.6	
300	97.8	
212	90.3	
150	66.8	
75	13.8	



REMARKS

SIGNED J. - Rama MATERIALS ENGINEER

DATE.....


Figure 6

42a SEAFIELD ROAD LONGMAN INDUSTRIAL ESTATE INVERNESS Telephone (0463) 225844

HIGHLAND TESTING SERVICES LTD.



PARTICLE SIZE DISTRIBUTION



Sample Ref. | DATE 5/3/87

SCHE SCHE

SCHEME Housing Scheme, Dornoch, LOCATION


SAMPLED

DATE

Client :-

Scott, Wilson, Kirkpatrick

HIGHLAND TESTING SERVICES LTD.



(Inverness)——


42a SEAFIELD ROAD LONGMAN INDUSTRIAL ESTATE INVERNESS Telephone (0463) 225844 MATERIALS TESTING ENGINEERS AND CONSULTING TECHNOLOGISTS

SAMPLE NO...B

	SAMPLE REF. 5231
CLIENT Scott, Wilson, Kirkpatrick Ltd	MATERIAL Sand (brown)
CONTRACT Housing Scheme, Dornoch	SUPPLIER
LOCATION	SOURCE
DATE RECEIVED. 5.3.87	B.S. APPLICABLE

AGGREGATE GRADING ANALYSIS

		
B.S. Sieve Size	Cumulati	ve Percentages Passing
Metric		Spec.
75mm		
63mm		
50 mm		
37.5 mm		
28 mm		
20 mm	100.0	
14 mm	97.8	
,10 mm	96.2	
6.3 mm	93.7	
5 mm	93.5	
3.35 mm	92.9	
2.36 mm	92.3	
1.18 mm	90.6	
mلر 600	77.9	
425	60.8	
300	36.4	
212	13.6	
150	4.3	
75	0.8	



REMARKS

SIGNED D. S. Barry MAS TRIALS ENGINEER

DATE.....

Scott, Wilson, Kirkpatrick

Client

DESCRIPTION.

Ξ

SCHEME Housing Scheme, Dornoch, LOCATION

SAMPLED

DATE

DATE 5/3/87

5231

Sample Ref.


LONGMAN INDUSTRIAL ESTATE 42a SEAFIÈLD ROAD INVERNESS


Telephone (0463) 225844


HIGHLAND TESTING SERVICES LTD.




PARTICLE SIZE DISTRIBUTION










กับราชเบก

SCOTT WILSON KIRKPATRICK & PARTNERS Chartered Engineers				SKETCH				Job No 8 7 504		RE 12	Revis	
			Revisi	on	Suffix							
					Date							
Date	Initials	Checked	Job	PROPOS	ED	HOUSI	NG	SCHEN	1E	J		
MAR' 87	DJB] :	SUTHER	RLAND	ROAL	DO CO	RNOC	Н.			
			R	unning ed	ge of	carriagev	ay.					



ACCESS ROAD PAVEMENT RECOMMENDED CONSTRUCTION

NOTES

- 1. All materials, laying and compaction to be in accordance with the DOT "Specification for Road and Bridge Works."
- 2. DBM Wearing Course to have 10 mm aggregate.

 DBM Base Course to have 20 mm aggregate.